

County	Name of Water Supply	Scheme Code	Population Served	Volume Supplied (m3/day)	Proposed Action Programme	Proposed Date of Completion of Action Programme (This is the date by which works are complete. There will be a further period to demonstrate the effectiveness of works before the supply is removed from the RAL.)	RAL Category: Inadequate Treatment for Cryptosporidium	RAL Category: Inadequate Treatment - Inadequate Disinfection	RAL Category: Failed to meet E coli/Enterococci standard in the Drinking Water Regulations	RAL Category: Elevated Levels of THMs above the standard in the Drinking Water Regulations	RAL Category: Elevated Levels of Pesticides above the standard in the Drinking Water Regulations	RAL Category: Supply identified by the HSE where further investigation or improvement may be required	RAL Category: Excessive levels of aluminium in the treated water	RAL Category: Poor turbidity removal	RAL Category: EPA Audit Observation - Treatment and Management Issues
Carlow	Carlow North Regional	0100PUB1142	8,460	7,083	Upgrade of water treatment plant	December 2024									Y
Clare	Corofin	0300PUB1010	1,319	326	Upgrade of water treatment plant	Complete and awaiting verification of the effectiveness of the action programme							Y		Y
Clare	Ennistymon RWS	0300PUB1004	6,492	6,389	Upgrade of water treatment plant	September 2024									Y
Clare	West Clare RWS (New WTP)	0300PUB1066	8,702	14,888	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann				Y					Y
Clare	West Clare RWS (Old WTP)	0300PUB1022	3,028	2,256	Existing plant to be replaced with new package plant.	December 2026				Y					Y
Cork	Killavullen	0500PUB1310	791	423	Rationalisation of supply	March 2024								Y	
Cork	Mitchelstown North	0500PUB1506	2,317	1,333	Installation of GAC system for removal of organics to minimise THM formation	June 2025				Y					
Cork	Ballyclough & Mount North	0500PUB1316	1,977	379	Disinfection upgrade for Mountnorth WTP	December 2024	Y								
Cork	Castletownbere	0500PUB4205	2,328	2,029	installation of GAC for removal of organics to minimise THM formation.	December 2028				Y					
Cork	Fermoy	0500PUB1207	7,381	3,379	Installation of UV disinfection	Complete and awaiting verification of the effectiveness of the action programme	Y								
Cork	Glashaboy	0500PUB3303	23,087	19,143	Upgrade of water treatment plant	June 2025									Y
Cork	Macroom	0500PUB2307	4,237	1,576	Upgrade water treatment plant	June 2025									Y
Cork	Newmarket	0500PUB1601	9724	8150	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann	Y								
Cork	Whiddy Island	0500PUB4108	47	24	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann						Y			
Cork	Whitegate Regional	0500PUB2407	9,011	5,497	Upgrade of water treatment plant	June 2027								Y	Y
Donegal	Lettermacaward	0600PUB1069	2,266	1843	Upgrade of water treatment plant.	December 2024				Y			Y		
Donegal	Glenties-Ardara	0600PUB1070	3,518	1,708	Installation of membrane filtration system to address the raw water colour and organic content, and minimise THM formation	September 2024				Y					
Donegal	Milford	0600PUB1050	3,714	2,296	Upgrade of filtration including GAC	June 2026				Y					
Galway	Inisboffin	1200PUB1024	156	269	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann									Y
Kerry	Cahersiveen	1300PUB1050	1,500	1,396	Crypto risk: Installation of UV disinfection. THM risk: Installation of GAC post slow sand filtration.	EPA Direction required compliance with THM limit by December 2023. Uisce Éireann proposed completion date for THM and crypto risk is June 2024.	Y			Y					
Kerry	Caragh Lake	1300PUB1046	1,886	1,159	Upgrade of water treatment plant.	THM Risk: Complete and awaiting verification of the effectiveness of the action programme. EPA Audit Observations: December 2024				Y					Y
Kerry	Listowel Regional Public Water Supply	1300PUB1204	14905	10,107	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Kerry	Kilgarvan	1300PUB1059	656	343	Installation of GAC post slow sand filters	December 2024				Y					
Kerry	Lyreacrompane	1300PUB1009	2,490	2100	Develop new groundwater sources and upgrade of water treatment plant	December 2029				Y					
Kerry	Mid Kerry/Gearha (H) 300A	1300PUB1063	9,207	7,132	To be submitted by Uisce Éireann	To be submitted by Uisce Éireann	Y								
Kildare	Barrow supply (Srowland WTP) <sup>1</sup>	1400PUB1060	80,592	40,654	Upgrade of Srowland WTP	December 2026									Y
Kilkenny	Kilkenny City (Radestown) WS	1500PUB1010	14,162	4,812	Abandon source of water supply and replace with Troyswood PWS	EPA Direction required compliance by June 2022. Uisce Éireann has provided a proposed completion date of March 2024.				Y					
Kilkenny	South Kilkenny	1500PUB1020	6,028	2,591	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann	Y								
Limerick	Limerick City Environs	1900PUB1032	114,764	44,501	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Limerick	Foynes/Shannon Estuary PWS	1900PUB1027	6,986	18,899	Pesticides risk: To be submitted by Uisce Éireann. Crypto risk: Installation of UV.	Pesticides risk: EPA Direction required compliance by April 2023. Crypto risk: March 2024.	Y				Y				
Longford	Longford Central	2000PUB1010	17,354	7,561	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Louth	Cavanhill	2100PUB1018	46,730	15,783	To be submitted by Uisce Éireann	To be submitted by Uisce Éireann				Y					Y
Louth	Greenmount	2100PUB1002	3,836	1,181	Upgrade of treatment facilities.	September 2026									Y
Louth	Tallanstown	2100PUB1005	2,010	431	Replacement of supply with Cavanhill PWS	EPA Direction required compliance by December 2020. Uisce Éireann has provided a proposed completion date of June 2024.							Y		Y
Mayo	Clare Island	2200PUB1030	160	75	To be submitted by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Mayo	Louisburgh	2200PUB1020	824	339	Abandon source and connect to Westport PWS (via Murrisk Group Water Scheme)	November 2028									Y
Meath	Drumcondrath	2300PUB1005	1,151	586	Develop new groundwater sources and upgrade water treatment plant	EPA Direction required compliance by June 2023. Uisce Éireann has provided a proposed completion date of June 2026.	Y			Y					
Meath	Navan - Mid Meath Kilcarn PWS	2300PUB1051	10,360	2,667	Replace DAFF with new CFC and filtration.	June 2026				Y					
Meath	Trim PWS	2300PUB1009	11,244	3,242	Upgrade of water treatment plant	December 2025									Y
Monaghan	Clones	2400PUB1002	2,658	907	To be submitted by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Offaly	Clara/Ferbane RWSS	2500PUB1003	7,341	2,497	Upgrade of water treatment plant	June 2024				Y					
Roscommon	North East Regional	2600PUB1030	7,997	3,894	Process review/optimisation/trial as well as network/reservoir cleaning and scouring.	March 2025				Y					
Tipperary	Carrick-on-Suir (Lingaun River)	2900PUB0108	3,784	1,176	To be submitted by Uisce Éireann	To be submitted by Uisce Éireann	Y								
Tipperary	Clonmel Poulavanogue	2900PUB0109	2,435	1,857	Rationalisation of water treatment plant	December 2026	Y								
Tipperary	Galtee Regional	2900PUB0130	11,379	8,912	Further upgrade of water treatment plant	March 2027							Y	Y	Y

County	Name of Water Supply	Scheme Code	Population Served	Volume Supplied (m3/day)	Proposed Action Programme	Proposed Date of Completion of Action Programme (This is the date by which works are complete. There will be a further period to demonstrate the effectiveness of works before the supply is removed from the RAL.)	RAL Category: Inadequate Treatment for Cryptosporidium	RAL Category: Inadequate Treatment - Inadequate Disinfection	RAL Category: Failed to meet E coli/Enterococci standard in the Drinking Water Regulations	RAL Category: Elevated Levels of THMs above the standard in the Drinking Water Regulations	RAL Category: Elevated Levels of Pesticides above the standard in the Drinking Water Regulations	RAL Category: Supply identified by the HSE where further investigation or improvement may be required	RAL Category: Excessive levels of aluminium in the treated water	RAL Category: Poor turbidity removal	RAL Category: EPA Audit Observation - Treatment and Management Issues
Tipperary	Kilcash	2900PUB0147	221	60	Rationalisation of supply	June 2028	Y								
Tipperary	Nenagh Regional	2800PUB1008	14,483	6,474	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Tipperary	Glengar	2900PUB0202	470	247	Rationalisation of supply	June 2024	Y								
Tipperary	Roscrea	2800PUB1009	6,103	818	Upgrade of water treatment plant.	March 2027	Y								
Tipperary	Templetuohy	2800PUB1013	799	144	Upgrade of water treatment plant.	March 2026	Y								
Tipperary	Thurles Regional	3700PUB1042	11,394	4,510	Action Programme being defined by Uisce Éireann	To be submitted by Uisce Éireann				Y					
Waterford	Graiguenagee	3100PUB1051	43	11	Abandon source and connect to Stradbally PWS	June 2024		Y							
Waterford	Dungarvan	3100PUB1039	12,687	5,649	Construction of new water treatment plant	May 2027								Y	
Wexford	Enniscorthy	3300PUB1491	11,448	618	Upgrade of water treatment plant.	June 2025	Y								Y
Wexford	Wexford Town	3300PUB1669	20,853	6,369	Upgrade of water treatment plant	June 2025									Y
Wicklow	Aughrim / Annacurra	3400PUB1023	1,583	340	Abandon source and connect to Arklow water treatment plant	EPA Direction required compliance by December 2023. Works complete and awaiting verification of the effectiveness of the action programme.				Y					
Wicklow	Ballymorris	3400PUB1076	16	5	Abandon source and connect to Arklow water treatment plant	January 2024		Y						Y	

1. Srowland WTP fully feeds the Barrow supply and partially feeds the Barrow Poulaphouca PWS (1400PUB1070), Monasterevin PWS (1400PUB1020) and Rathangan PWS (1400PUB1041).